

Digital Projection Titan Laser 33000 4K-UHD

DIGITAL PROJECTION TITAN LASER



Brief Introduction

Beta 2.5

The Digital Projection model Titan Laser 33000 4K-UHD is a DLP laser projector with UHD (4K2K) 3840 x 2160 resolution and a contrast of 18000:1. It is a laser projector with 20000 hours of light life, which is over 13.7 years if enjoyed for four hours a day. A picture width of up to 1745 cm is possible, if the picture width is smaller (we recommend max. 1163 cm), rooms with residual light are also no problem. In the event that the image is still too small, the projector offers integrated edge blending software, which allows several projectors to project a large image together. Furthermore, it is Full HD 1080P and 4K as well as 3D compatible, meaning that all currently available Blu-ray formats can be recognized by the projector. The model was built by Digital Projection in 2018 and is no longer current.

 3 x 0,96" DMD Chip
UHD 16/9 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen
Contrast
Black Level
Offset
Resolution
Video Modes
3D Compatibility
Application
Light Source
Light Life

Projector	29500	Screen	13111 Lux (bei 200 cm Screen)
	18000:1 full on/off		18000:1 full on/off
	1,6389 min. Lumen		0,728 min. Lumen
	-		
	UHD (4K2K) 3840 x 2160		
	8.294.400 Pixel		
	Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 4K UHD, 3D, EDTV 480p, 576p		
	Frame-Packing (Full HD 3D) Side-by-Side Top-and-Bottom		
	Frame Sequential (3D Ready)		
	Event Very large screen width and rooms with plenty of light and shaded daylight.		
	Laser		
	20000 h.		

Operating Costs

0,00 € Laser

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio


optional

Audio

-

Connections

4 x HDMI in (1.4b /2.0b)
Display Port 1.2
3G SDI in und out
3D Sync in und out
Wired Remote



	12 V trigger out
	3d Sync IR out
	RS232C Din 9 pin in
	2 x RJ45 in
	HDBaseT
Ceiling Mounting	Yes
Power	3400W
Size WxHxD	930 x 350 x 650 mm (36,6"x13,8"x25,6") 211,58 L/dm³
Operating Noise	50 / 47 dB in Eco Mode

Weight	99,00 kg / 218,26 lbs.
Keystone	-
Illumination	-

Frequenz	-
----------	---

Foot-Lamberts	1218 fL / max. 1745 cm screen width 4173 cd/m²
---------------	---

- Real Full HD 3D

Full HD 1080P compatible

Eco Mode

High Dynamic Range (HDR)

Edge Blending

Picture-in-Picture

Lan network compatible.

Crestron®-Software compatible.


AMX

DICOM simulation mode. DMX

Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
109-236	1.16-1.49:1	2.3-3 m	+/-50%	+/-18%	Powered
109-235	6.92-10.36:1	13.8-20.7 m	70-50%	+/-18.75%	Powered
105-613	4.16-6.96:1	8.3-13.9 m	70-50%	+/-18.75%	Powered
105-612	2.56-4.16:1	5.1-8.3 m	70-50%	+/-18.75%	Powered
105-611	1.87-2.56:1	3.7-5.1 m	70-50%	+/-18.75%	Powered
105-610	1.39-1.87:1	2.8-3.7 m	70-50%	+/-18.75%	Powered
Fix Optional Lenses					
105-608	1.12:1	2.2 m	70-50%	+/-18.75%	No Zoom
105-607	0.67:1	1.3 m	+/-10%	+/-10%	No Zoom

Status

2018 Discontinued (EOL) // Last update of the data: 2024-10-02
Created: 2018-11-11 13:32:27



More Details

HCinema

<https://www.projector-database.com/pro/digitalprojectiontitanlaser330004kuhd-en.html>