

Digital Projection TITAN sx+ 660 Ultra Contrast



Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Lens shift

Resolution

Video Modes

3D Compatibility

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Connections

Ceiling Mounting

Power

Size WxHxD

Operating Noise

A brief introduction to the Digital Projection TITAN sx+ 660 Ultra Contrast. The stationary DLP projector has an SXGA+ 1400 x 1050 resolution and a contrast of 4000:1. The integrated lens shift gives freedom when positioning the projector. Thanks to the brightness of 5000 Ansi lumens, an image width of 616 cm is possible. The projector will also create slightly brighter rooms with a smaller image width (we recommend max. 411 cm). Furthermore, the projector can play 1080P and 3D without any problems. The model was built by Digital Projection in 2012 and is no longer current, but is still one of the very popular projectors.



3 x 0,95" 12 Grad DLP Chip
SXGA 4/3 Ti Digital Light Processing Chip

Projector

5000

4000:1 full on/off

1,2500 min. Lumen

Vert.: +50% -40% Hori.: +/-20%

SXGA+ 1400 x 1050

1.470.000 Pixel

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom

Frame Sequential (3D Ready)

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

2 x 330W Lamp

Article Nr.: 109-319

1500 h. 3000 h. in Eco Mode

-

Powered

Powered

optional

optional

Nein

HDMI 1.4

DVI in

D-sub 15 pin in

5 x BNC RGBHV in

YUV über BNC in

BNC Video in

RJ45 in

RS232C

Yes, is possible.

950W

568,50 x 253,5 x 464,0 mm (22,4"x10"x18,3") 66,68 L/dm³


45dB

Screen


1667 Lux (bei 200 cm Screen)

4000:1 full on/off

0,417 min. Lumen



Weight	36,00 kg / 79,37 lbs.
Keystone	-
Illumination	87%
Frequenz	H-sync: 15-100 kHz V-sync: 24-85 Hz
Foot-Lamberts	155 fL / max. 616 cm screen width 531 cd/m ²
Features	■ Real Full HD 3D
	■ Full HD 1080P compatible
	■ Lens shift Funktion
	■ Freeze
	■ Eco Mode
	■ Gamma correction
	■ Password protection
	■ Wi-Fi network compatible.
Screen Mirroring	■ Lan network compatible.
	-



Optional accessories

	Einzel Lampe Ruby	Ruby-LMP20266	321,57 €
	Einzel Lampe inkl. Luftfilter Original	111-258 / 109-319	EOL €
	Deckenhalterung	HeavyDuty	378,28 €

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
109-236	1.26-1.61:1	2.5-3.2 m	+/-36%	+/-20%	Powered
109-235	7.5-11.2:1	15-22.4 m	50-40%	+/-20%	Powered
105-613	4.51-7.53:1	9-15.1 m	50-40%	+/-20%	
105-612	2.77-4.51:1	5.5-9 m	50-40%	+/-20%	Powered
105-611	2.02-2.77:1	4-5.5 m	50-40%	+/-20%	Powered
105-610	1.5-2.02:1	3-4 m	50-40%	+/-20%	Powered
Fix Optional Lenses					
105-609	1.12:1	2.2 m	50-40%	+/-20%	
105-608	1.2:1	2.4 m	50-40%	+/-20%	No Zoom
105-607	0.73:1	1.5 m	+/-11%	+/-7%	No Zoom

Status 2012 Discontinued (EOL) // Last update of the data: 2025-03-03
Created: 2012-11-09 11:41:53

Data

More Details



HCinema
<https://www.projector-database.com/pro/digitalprojectiontitansxplus660ultracontrast-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.