

Digital Projection TITAN WUXGA 660 Ultra Contrast neu



Brief Introduction Beta 2.5

With the TITAN WUXGA 660 Ultra Contrast, manufacturer Digital Projection now offers a DLP projector with WUXGA 1920 x 1200 resolution and a contrast of 4000:1. The projector also offers a lens shift function, which makes setting up the image childs play. The projector can illuminate images up to 787 cm wide thanks to its 6000 Ansi lumens. The projector can create rooms with residual light with a smaller image width, we recommend a maximum of 525 cm. Video signals 1080P and 3D are also no problem for the projector. The model was built by Digital Projection in 2012 and is no longer current.



3 x 0,97" 12 Grad DLP Chip

WUXGA 16/9 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

6000

2667 Lux (bei 200 cm Screen)

Contrast

4000:1 full on/off

4000:1 full on/off

Black Level

1,5000 min. Lumen

0,667 min. Lumen

Lens shift

Vert.: +70% -50% Hori.: +/-18,7%

Resolution

WUXGA 1920 x 1200

2.304.000 Pixel

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

3D Compatibility

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom

Frame Sequential (3D Ready)

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

Light Source

2 x 330W Lamp

Article Nr.: 109-319

Light Life

1500 h. 3000 h. in Eco Mode

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

Nein

HDMI in

DVI in

D-sub 15 pin in

Connections

5 x BNC RGBHV in

YUV über BNC in

BNC Video in

RJ45 in

RS232C

Ceiling Mounting

Yes, is possible.

Power


950W

Size WxHxD


543,5 x 253,5 x 645,4 mm (21,4"x10"x25,4") 88,61 L/dm³

Operating Noise

45dB



Weight	36,00 kg / 79,37 lbs.
Keystone	-
Illumination	87%
Frequenz	H-sync: 15-100 kHz V-sync: 24-85 Hz
Foot-Lamberts	248 fL / max. 787 cm screen width 850 cd/m²
Features	■ Real Full HD 3D
	■ Full HD 1080P compatible
	■ Lens shift Funktion
	■ Freeze
	■ Eco Mode
	■ Gamma correction
	■ Password protection
Screen Mirroring	■ Wi-Fi network compatible.
	■ Lan network compatible.
	■



Optional accessories

	Einzel Lampe Ruby	Ruby-LMP20266	321,57 €
	Lampe Original	109-319	EOL €
	Einzel Lampe inkl. Luftfilter Original	111-258 / 109-319	EOL €
	Deckenhalterung	HeavyDuty	378,28 €

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
109-236	1.16-1.87:1	2.3-3.7 m	70-50%	+/-18.75%	Powered
109-235	6.92-10.36:1	13.8-20.7 m	70-50%	+/-18.75%	Powered
105-613	4.16-6.96:1	8.3-13.9 m	70-50%	+/-18.75%	
105-612	2.56-4.16:1	5.1-8.3 m	70-50%	+/-18.75%	Powered
105-611	1.87-2.56:1	3.7-5.1 m	70-50%	+/-18.75%	Powered
105-610	1.39-1.87:1	2.8-3.7 m	70-50%	+/-18.75%	Powered
Fix Optional Lenses					
105-609	1.12:1	2.2 m	70-50%	+/-18.75%	
105-608	1.12:1	2.2 m	70-50%	+/-18.75%	No Zoom
105-607	0.67:1	1.3 m	+/-10%	+/-10%	No Zoom

Status 2012 Discontinued (EOL) // Last update of the data: 2025-03-03
 Data Created: 2012-11-08 16:11:42

More Details



HCinema
<https://www.projector-database.com/pro/digitalprojectiontitanwuxga660ucneu-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice.
 HCinema is not responsible for any errors or omissions contained in product descriptions.