

Geha compact 145

GEHA COMPACT 145



Brief Introduction

Beta 2.5

The Geha compact 145 standard portable LCD projector has 1400 Ansi lumens, a contrast of 400:1 and an SVGA 800 x 600 resolution. Due to the brightness of 1400 Ansi lumens, a picture width of 326 cm is possible. In room light, the picture should be max. 217 cm wide. The model was built by Geha in 2004 and is no longer current. It should also be noted that, unfortunately, there are no more replacement lamps for the projector, neither originals nor replicas.

Display Type



3 x 0,7" LCD TFT Panel
SVGA 4/3 Liquid Crystal Display

Ansi-Lumen

1400 / vor Cebit 2004 1200

453 Lux (bei 203 cm Screen)

Contrast

400:1 full on/off

400:1 full on/off

Black Level

3,5000 min. Lumen

1.141 min. Lumen

Offset

-

Resolution

SVGA 800 x 600

480.000 Pixel

XGA 1024 x 768 compressed

Video Modes

PAL, SECAM, NTSC 3.58/4.43 HDTV

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

150W UHP Lamp

Articel Nr.: 60 258461

Light Life

2000 h.

Operating Costs

-

Focus

-

Zoom

-

Objective

-

Throw Ratio

-

Audio

1 x 1W

Connections

D-sub 15pin in und out

2 x Cinch Stereo in

Cinch Video in

S-Video

USB

Ceiling Mounting

Yes

Power


-

Size WxHxD

313 x 99 x 272 mm (12,3"x3,9"x10,7") 8,43 L/dm³

Operating Noise

36dB



Weight	2,70 kg / 5,95 lbs.
Keystone	Vert.: +/-15°
Illumination	-
Frequenz	H-sync: 30-70 kHz V-sync: 56-85 Hz
Foot-Lamberts	42 fL / max. 326 cm screen width 144 cd/m²
Features	-
Status	2004 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/gehacompact145-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.