

Jmgo E8

J M G O E 8



A brief introduction to the E8: The Jmgo 3D DLP projector offers 750 Ansi lumens, a contrast of 3000-5000:1 and a WXGA 1280 x 800 resolution. An image width of up to 278 cm is possible as the projector has 750 Ansi lumens. However, if room light is available, the image should be max. 185 cm wide. The model recognizes screen mirroring signals, so it is possible to play videos with high resolution and surround sound directly via WLAN from a smartphone, tablet or PC (Android, Windows and iOS). It is also Full HD 1080P and 3D compatible. The model was built by Jmgo in 2017 and is no longer current.

 1 x 0,45" DMD Chip
WXGA 16/10 Ti Digital Light Processing Chip

Projector	750	300 Lux (bei 200 cm Screen)
Contrast	3000-5000:1 full on/off	3000-5000:1 full on/off
Black Level Offset	0,2500 min. Lumen	0,1 min. Lumen

Resolution: WXGA 1280 x 800
1.024.000 Pixel
Video Modes: Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p
3D Compatibility: Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom
Frame Sequential (3D Ready)
Application: Standard-Portabel | External training and company presentations, as well as product presentations.
Light Source: LED RGB
Light Life: -
Operating Costs: 0,00 € LED
Focus: Powered
Zoom: No Zoom
Objective: -
Throw Ratio: 1,2:1
Audio: -

Small screen width, rooms with very little ambient light below 100 lumens.



Connections: HDMI in, AV Jack in, Mini Jack Audio out, 2 x USB (1x 3.0) in, RJ45 in
Ceiling Mounting: Yes
Power: 45W
Size WxHxD: 194,5 x 48 x 194,5 mm (7,6"x1,9"x7,6") 1,81 L/dm³

Brief Introduction
Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Offset

Resolution

Video Modes

3D Compatibility

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Connections

Ceiling Mounting

Power

Size WxHxD

Operating Noise -

Weight -

Keystone Vert.: +/-40°



Illumination -

Frequenz -

Foot-Lamberts 28 fL / max. 278 cm screen width
96 cd/m²

- Features
- Real Full HD 3D
 - Full HD 1080P compatible
 - Wi-Fi network compatible.
 - Lan network compatible.
 - Bluetooth
 - 4-Core CPU / 1GB DDR3 / 16 GB eMMC
 - Android 4.4

Status 2017 Discontinued (EOL) // Last update of the data: 2024-05-16



More Details



HCinema

<https://www.projector-database.com/pro/jmgoe8-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.