

Optoma P771



OPTOMA P771



Brief Introduction

Beta 2.5

A brief introduction to the Optoma P771. The DLP projector has an XGA 1024 x 768 resolution and a contrast of 10000:1. Thanks to the lamp, the projector has a lamp life of up to 3500 hours, which is over 4.8 years if enjoyed for two hours a day. The projector will be able to illuminate a screen width of 515 cm. Rooms with residual light can be created by the projector with a smaller image width, max. 343 cm is recommended here. The model is also Full HD 1080P compatible. The model was built by Optoma in 2013 and is no longer current.



1 x 0,55" DLP Chip

XGA 4/3 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

3500

1167 Lux (bei 200 cm Screen)

Contrast

10000:1 full on/off

10000:1 full on/off

Black Level

0,3500 min. Lumen

0,117 min. Lumen

Offset

Resolution

XGA 1024 x 768

786.432 Pixel

UXGA 1600 x 1200 compressed

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Source

-

Light Life

3500 h. 5000 h. in Eco Mode

Operating Costs

-

Focus

Manual

Zoom

Manual 1,1

Objective

F=2,51-2,69 f=21,95-24,18 mm

Throw Ratio

1,97-2,17:1

Audio

8W

HDMI in

2 x D-Sub 15 pin in 1 x out

S-Video in

Cinch Video in

Mini Jack Audio in und out

RS232C

mini USB in

RJ45 in

Connections



Ceiling Mounting

Yes

Power


325W

Size WxHxD

280 x 78,4 x 230 mm (11"x3,1"x9,1") 5,02 L/dm³

Operating Noise

32dB



Weight	2,20 kg / 4,41 lbs.
Keystone	Vert.: +/-20°
Illumination	85%
Frequenz	H-sync: 15,3-91,10 kHz V-sync: 24-85 Hz
Foot-Lamberts	108 fL / max. 515 cm screen width 370 cd/m²
Features	■ Full HD 1080P compatible ■ Eco Mode ■ Lan network compatible.
Status	2013 Discontinued (EOL) // Last update of the data: 2023-08-07
Data	Created: 2013-05-29 13:16:59



More Details



HCinema

<https://www.projector-database.com/pro/optomap771-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.